



Technical Report No.: 64.181.23.03010.01 Rev.00

Date: 2023-08-09

		Date: 2020-00-03
Client:	Report holder's name:	Sonnenwärme Direkt GmbH
	Report holder's Address:	Dammholmer Str. 3, 24873 Havetoft, Germany
	Contact person of report holder:	Guido Arntz
Manufacturer:	Manufacturer's name:	Sonnenwärme Direkt GmbH
	Manufacturer's address:	Dammholmer Str. 3, 24873 Havetoft, Germany
Test object:	Product:	DC Inverter Heat Pump
	Model:	SWD WP10 R290, SWD WP15 R290
	Trade mark:	
Test specification:	<b>V</b>	EN 14825:2022
	<b>✓</b>	EN 12102-1:2022
	<b>✓</b>	EN 14511-3:2022
	<b>V</b>	EN 14511-4:2022 Clause 4
Purpose of examination:	Test according to the to	est specification
cxammaton.	<b>✓</b>	(EU) No 813/2013
	<b>V</b>	EU 2016/2282:2016-11-30
Test result:	The test results show t listed test specification	hat the presented product is in compliance with the above s.

Any use for advertising purposes must be granted in writing. This technical report may only be quoted in full. This report is the result of a single examination of the object in question. It does not imply a general statement regarding the quality of products from regular production. For further details please see testing and certification regulation, chapter A-3.4.

Rev.: 00 Date: 2023-08-09 Page: 1 of 32

www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch, TÜV SÜD Group 5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Aye. West, Guangzhou 510656, China



# 1 Description of the test object

#### 1.1 Function

Manufacturer's specification for intended use: The appliance is air to water heat pump. Manufacturer's specification for predictive use: According to user manual

12	Consideration	of the	foreseeable	HSE
1.4	CONSIDERATION	OI LIIC	IUICSCCADIC	usc

	Not applicable
<b>√</b>	Covered through the applied standard
	Covered by the following comment
	Covered by attached risk analysis

#### 1.3 Technical Data

Rated Voltage (V): 380-415V, 3N~

Rated Frequency (Hz): 50

Rated Power (W): 2080W for SWD WP10 R290,

2800W for SWD WP15 R290

Rated Current (A): 3.72A for SWD WP10 R290,

5.01A for SWD WP15 R290

Protection Class: Class I
Protection Against Moisture: IP X4
Construction: Stationary

Supply connection : 

Non detachable cord

Permanent connection to fixed wiring

Operation mode: 

Continuous operation;

Intermittent operation;Short time operation;

Refrigerant/charge (kg): R290 / 1.15kg for SWD WP10 R290,

1.40kg for SWD WP15 R290

Declared parameters : 

☑ Average □ Warmer □ Colder

Sound power level dB(A): N/A

Series No: PPAL05023041331 for SWD WP10 R290,

PPAL06023010054 for SWD WP15 R290

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 2 of 32 www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch, TÜV SÜD Group

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



#### 2 Order

#### 2.1 Date of Purchase Order, Customer's Reference

Date of Purchase Order: 2023-01-09, 2023-02-09, 2023-07-27

Customer's Reference: Sonnenwärme Direkt GmbH

2.2 Test Sample(s)

Reception date(s): 2023-04-01, 2023-06-08

• Location(s) of reception:

For Energy test:

Guangzhou Customs District Technology Center

Address: No.3, Desheng East Road, Daliang, Shunde District, Foshan, Guangdong, China

For Noise tests:

CVC Testing Technology Co., Ltd.

Address: No.3, Tiantaiyi Road, Kaitai Avenue, Science City, Guangzhou, Guangdong, 510663, P.R.China

Condition of test sample(s): completed and can be normal operation

#### 2.3 Date(s) of Testing

2023-04-01 to 2023-04-28, 2023-06-08 to 2023-06-10

### 2.4 Location(s) of Testing

Same as 2.2

# 2.5 Points of Non-compliance or Exceptions of the Test Procedure

### 3 Test Results

☑ Decision rule according to ILAC-G8:09/2019 clause 4.2.1 Binary statement for simple
acceptance rule or IEC Guide 115:2021, clause 4.4.3, 4.5.1 Accuracy method was
applied

- ☐ Decision rule according to customer's requirements was applied. It is:
- □ Decision rule according to ILAC-G8:09/2019 clause 4.2.2 Binary statement with guard band guard band length = 95 % extended measurement uncertainty, was applied.
- □ Decision rule (based on ILAC-G8:09/2019 clause 4.2.3 Non-binary statement with guard band, guard band length = 95 % extended measurement uncertainty) for an upper specification limit (A lower limit or specification with an up-per and a lower limit is treated similarly.):
- Compliance with the requirement: If a specification limit is not breached by a measurement result plus the expanded uncertainty with a 95% coverage probability, then compliance with the specification will be stated (e. g. Pass).
- Non-compliance with the requirement: If a specification limit is exceeded by the measurement result minus the expanded uncertainty with a 95% coverage probability, then non-compliance with the specification will be stated (e. g. Fail).
- Inconclusive result: If a measurement result plus/minus the expanded uncertainty with a 95 % coverage probability overlaps the limit it will be stated that it is not possible to state compliance or non-compliance.

#### 3.1 Positive Test Results

See Appendix I

Project No: 64.181.23.03010.01 Rev.: 00 Date: 2023-08-09 Page: 3 of 32 www.tuvsud.com

∏"**\**/®

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch, TÜV SÜD Group

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



#### 4 Remarks

#### 4.1 General

The user manual has been examined according to the minimum requirements described in the product standard. The manufacturer is responsible for the accuracy of further par-ticulars as well as of the composition and layout.

**4.2** When the product is placed on the market, it must be accompanied with safety Instructions written in official language of the country. The instructions shall give information re-garding safe operation, installation and maintenance.

#### 5 Documentation

- Appendix I: Test results
- · Appendix II: Marking plate
- Appendix III: photo documentation
- Appendix IV: Construction data form
- Appendix V: Test equipment list

#### 6 Test History

- These appliances are Air To Water Heat Pump Unit, each one including a whole compression type refrigerant circuit to heat water in another circuit. These appliances were for cooling and heating water function, this report only for heating capacity test.
- 2) The main power is supplied by a 5-pole supply cord connecting to fixed wiring.
- 3) Water enthalpy method was adopted in this report.
- 4) Standby mode power, off mode power and thermostat-off mode power were tested according to clause 12 of standard EN 14825:2022.
- 5) This test report 64.181.23.02546.01 Rev.00, dated 2023-08-09 bases on original test report 64.181.23.00458.02 Rev.00, dated 2023-06-20 to include the following changes and/or additions, which were considered technical modifications:
  - a) Changing report holder name and address, manufacturer name and address, trademark and model name.
  - b) After evaluating, no additional test was needed.

# TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch TÜV SÜD Group

Tested by: William Liang, Project Handje

printed name, function & signature

Approved by: Plum Li, Designated Reviewe

printed name, function & signature

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 4 of 32 www.tuvsud.com

TÜV®

Road, Huangpu Ave. West, Guangzhou 510656, China



Appendix I 1	est results								
Table 1.	Heating mod	e(Low temp	erature	applica	tion):			F	•
Model	SWD WP10 F	R290							
Product type	Air to Water	Heating season	V	Averag e		Warme		Colder	
1. Test cond	itions:								
		Part Loa		ı		Outdoo excha		Indoo excha	r heat
Condition	Form		A	W	С	Inlet dr			let water
뎔	10111	luiu		**		bu			ures (°C)
ပိ						tempe	rature		55 ( 5)
Α	(-7-16)/(Tdesi	gnh-16)	88	N/A	N/A	-7(	-8)	a/	34
В	(+2-16)/ (Tdes		54	N/A	N/A	2(		a/	
С	(+7-16)/(Tdes		35	N/A	N/A	7(		a /	
D	(+12-16)/(Tde		15	N/A	N/A	12(		a /	
E		TOL-16)/ (To				TO			35.3
F G		oivalent-16)/(			N/A	T <u>t</u> -1		a / N/	
	(-15-16)/(Tdes th the water flo		N/A	N/A					
	ditions, the cap								
2.Tested dat	a/correction	data(Avera	age):						
General test	Unit	A(-7)/W34	A2/	W30	A7/W2	7 A1	2/W24	A(-	A(-7)/
conditions/		(88%)	(54	4%)	(35%)	)   (1	5%)	10)/W35.	W34
Part-Load								3 (100%)	(88%)
		Α		В	С		D	Е	F
Data collection period	hh: min:sec	1:10:00	1:1	0:00	1:10:0	0 1:	10:00	1:10:00	1:10:00
The heat pump defrosts		No	١	No	No		No	No	No
Complete Cycles		0		0	0		0	0	0
Barometric pressure	kPa	101.02	10 <sup>-</sup>	1.01	101.0	1 10	1.02	101.01	101.02
Voltage	V	398.8	39	9.5	398.6	3	98.7	398.4	398.8
Current input of the unit	А	5.26	2.	.44	2.24	,	1.80	6.53	5.26
Power input of the unit	kW	2.851	1.2	260	1.128	0	.882	3.743	2.851
Test condition	s <b>indoor</b> unit								
<b>Inlet</b> Water temperature, DB	°C	28.92	26	5.93	25.01	2	3.11	29.63	28.92
Outlet Water temperature, DB	°C	33.99	30	0.00	28.77	2	6.93	35.30	33.99

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 5 of 32





Appendix I 1	est results							
Test condition	s <b>outdoor</b> unit							
Air <b>inlet</b> temperature, DB	°C	-7.00	2.03	7.01	12.00	-10.07	-7.00	
Air <b>inlet</b> temperature, WB	°C	-8.01	1.00	6.01	11.00	-11.03	-8.01	
Summary of th	ne results							
Total heating capacity	kW	9.080	5.539	6.732	6.852	10.137	9.080	
Effective power input	kW	2.816	1.225	1.092	0.847	3.708	2.816	
Coefficient of performance (COP)		3.23	4.52	6.16	8.09	2.73	3.23	
Compressor frequency	Hz	70	35	30	30	90	70	
Water flow	m³/h	1.55	1.55	1.55	1.55	1.55	1.55	
3.Calculatio	n/conclusion	o for SCOP	(Average):					
Tdesignh(°C)		1 101 0001	Tbiv(°C)	-7				
r doorgrin ( o)	'		15.1(0)	'				
Pdesignh(kW )	10.265		TOL(°C)	-10				
Test result A	A, B, C, D, E,	F condition	ns:					
Condition	Part load	Measured capacity	COP at measured capacity	Cdh	CR	COP at p	oart load	
E	10.265	10.137	2.73	0.90	1.00	2.	73	
F	9.080	9.080	3.23	0.90	1.00	3.2	23	
А	9.080	9.080	3.23	0.90	1.00	3.2	23	
В	5.527	5.539	4.52	0.90	1.00	4.5	52	
С	3.553	6.732	6.16	0.90	0.53	5.66		

Project No: 64.181.23.03010.01

1.579

CR: part load divided by capacity;

6.852

Rev.: 00 Date: 2023-08-09 Page: 6 of 32

D



8.09

0.90

0.23



6.07



Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.024
Standby mode [P <sub>SB</sub> ]	kW	0.007
Crankcase heater [P <sub>CK</sub> ]	kW	0.043
Off mode [P <sub>OFF</sub> ]	kW	0.007

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.61
SCOP:	kWh/kWh	4.60
Q <sub>H</sub> :	kWh/year	21207
Q <sub>HE</sub> :	kWh/year	4614
η <sub>s,h</sub>	%	180.8
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 7 of 32





Table 2.	Heating mod	e(Medium to	empera	ture app	lication)	:		F	•
Model	SWD WP10 F	WP10 R290					<u> </u>		
Product type	Air to Water	Heating season	7	Averag e		Warmer		Colder	
1. Test cond	litions:								
uo		Part Loa in '				Outdoo excha		Indoo excha	
Condition	Form	ula	A	W	С	Inlet dry bul temper °C	b ature	Inlet/outl temperat	et water ures (°C)
Α	(-7-16)/(Tdesi	gnh-16)	88	N/A	N/A	-7(-	8)	a/	52
В	(+2-16)/ (Tdes	signh-16)	54	N/A	N/A	2(1	)	a/	42
С	(+7-16)/(Tdes		35	N/A	N/A	7(6		a /	36
D	(+12-16)/(Tde	signh-16)	15	N/A	N/A	12(1	1)	a /	30
E		TOL-16)/ (To				ТО		a/5	55.3
F		oivalent-16)/				Tbi		a /	52
G	(-15-16)/(Tdes		N/A	N/A	N/A	-15		N/	
	ith the water flo aditions, the cap								
2.Tested dat	ta/correction	data(Aver	age):						
General test conditions/ Part-Load	Unit	A(-7)/W52 (88%)	1	W42 4%)	A7/W3 (35%)	l l	/W30 5%)	A(- 10)/W55. 3 (100%)	A(- 7)/W52 (88%)

Part-Load			, ,	, ,	,	3 (100%)	(88%)
		Α	В	С	D	E	F
Data collection period	hh: min:sec	1:10:00	1:10:00	1:10:00	1:10:00	1:10:00	1:10:00
The heat pump defrosts		No	No	No	No	No	No
Complete Cycles		0	0	0	0	0	0
Barometric pressure	kPa	99.85	99.85	99.85	99.80	99.75	99.85
Voltage	V	398.9	399.1	398.6	398.6	398.7	398.9
Current input of the unit	А	7.49	3.78	2.39	2.12	7.57	7.49
Power input of the unit	kW	4.508	2.018	1.229	1.064	4.587	4.508

Project No: 64.181.23.03010.01

Test conditions indoor unit

°C

°C

Rev.: 00 Date: 2023-08-09 Page: 8 of 32

Inlet Water

DB

DB

temperature,

Outlet Water temperature,

www.tuvsud.com

36.14

42.03

32.24

37.12



42.16

52.00

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

47.41

55.06

42.16

52.00

Tel: +86 20 38320668

28.33

34.13



Appendix I							
Test condition	s <b>outdoor</b> unit	:					
Air <b>inlet</b> temperature, DB	°C	-7.00	2.02	7.01	12.00	-10.06	-7.00
Air <b>inlet</b> temperature, WB	°C	-8.00	0.99	6.01	11.00	-11.05	-8.00
Summary of the	ne results						
Total heating capacity	kW	10.765	6.691	5.520	6.581	8.726	10.765
Effective power input	kW	4.497	2.007	1.217	1.053	4.576	4.497
Coefficient of performance (COP)		2.39	3.33	4.53	6.25	1.91	2.39
Compressor frequency	Hz	74	35	30	30	90	74
Water flow	m³/h	0.98	0.98	0.98	0.98	0.98	0.98
3.Calculatio Tdesignh(°C)	n/conclusior  -10	for SCOP	(Average):	-7			
, <b>g</b> ( -,			( _ ,				
Pdesignh(kW )	12.169		TOL(°C) -10				
Test result A	A, B, C, D, E,	F condition	ns:				
Condition	Part load	Measured capacity	COP at measured capacity	Cdh	CR	COP at	oart load
E	12.169	8.726	1.91	0.90	1.00	1.	91
F	10.765	10.765	2.39	0.90	1.00	2.	39
Α	10.765	10.765	2.39	0.90	1.00	2.	39
В	6.553	6.691	3.33	0.90	0.98	3.	33
С	4.212	5.520	4.53	0.90	0.76	4.	40
D	1.872	6.581	6.25	0.90	0.28	4.	99
CR: part load	divided by cap	acity;		<u> </u>			

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 9 of 32  $\underline{www.tuvsud.com}$ 





Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.024
Standby mode [P <sub>SB</sub> ]	kW	0.007
Crankcase heater [P <sub>CK</sub> ]	kW	0.043
Off mode [P <sub>OFF</sub> ]	kW	0.007

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.45
SCOP:	kWh/kWh	3.44
Q <sub>H</sub> :	kWh/year	25141
Q <sub>HE</sub> :	kWh/year	7302
$\eta_{s,h}$	%	134.7
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 10 of 32





Appendix I 1	Test results								
Table 3.	Heating mod		F	•					
Model	SWD WP15 F	₹290						•	
Product type	Air to Water	Heating season	7	Averag e		Warmer		Colder	
		oouso							
1. Test cond	litions:	D41	-I D -4:-			0.44.	I4	l to do a	4
<b>-</b>		Part Loadin 9				Outdoo excha		excha	r heat
Condition	Form		A	W	С	Inlet dry			let water
pu		laid	, ,	''	•	bul	. ,	temperat	
Co						temper °C	ature		
A	(-7-16)/(Tdesi		88	N/A	N/A	-7(-		a /	
B C	(+2-16)/ (Tde:		54	N/A	N/A N/A	2(1		a /	
D	(+7-16)/(Tdes (+12-16)/(Tde		35 15	N/A N/A	N/A N/A	7(6 12(1		a / a /	
E		(TOL-16)/ (To			14// 1	TO			35.3
L		oivalent-16)/(				Tbi	٧	a/	
G	(-15-16)/(Tde		N/A	N/A	N/A	-1:		N.	
	ith the water flood iditions, the ca								
2.Tested dat	ta/correction	data(Avera	• •						
General test	Unit	A(-7)/W34		W30	A7/W2		/W24	A(-	A(-7)/
conditions/		(88%)	(54	4%)	(35%)	)   (1	5%)	10)/W35.	W34
Part-Load								3 (100%)	(88%)
		A		В	С		D	E	F
Data collection period	hh: min:sec	1:10:00	1:1	0:00	1:10:0	0   1:1	0:00	1:10:00	1:10:00
The heat		No	١	10	No		No	No	No
pump defrosts									
Complete Cycles		0		0	0		0	0	0
Barometric pressure	kPa	101.02	10 <sup>-</sup>	1.01	101.0	1 10	1.02	101.01	101.02
Voltage	V	399.6	39	9.7	398.8	39	9.1	398.6	399.6
Current input of the unit	А	6.38	3.19		2.55	2	.26	8.33	6.38
Power input of the unit	kW	3.755	1.711 1.3		1.310	1.	141	5.103	3.755
Test condition	s <b>indoor</b> unit								
<b>Inlet</b> Water temperature, DB	°C	29.25	27	7.02	25.13	23	3.17	29.93	29.25
Outlet Water temperature,	°C	34.04	29	.94	28.26	26	3.63	35.31	34.04

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 11 of 32

DB

www.tuvsud.com

TÜV SÜD Certification and Testing (China) Co., Ltd. Guangzhou Branch, TÜV SÜD Group

5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China

Test condition	s <b>outdoor</b> unit							
Air <b>inlet</b> temperature, DB	°C	-7.08	2.02	7.01	12.02	-10.00	-7.08	
Air <b>inlet</b> temperature, WB	°C	-8.06	1.05	6.01	11.02	-11.04	-8.06	
Summary of the	Summary of the results							
Total heating capacity	kW	12.431	7.574	8.142	8.979	14.005	12.431	
Effective power input	kW	3.721	1.677	1.276	1.107	5.069	3.721	
Coefficient of performance (COP)		3.34	4.52	6.38	8.11	2.76	3.34	
Compressor frequency	Hz	70	35	30	30	90	70	
Water flow	m³/h	2.24	2.24	2.24	2.24	2.24	2.24	
Damanic		<u> </u>	·					

Remark: -

3.	Ca	lcu	lati	ion/	cond	clus	ion	for	SC	COF	<b>?</b> (/	4ve	rage	):
----	----	-----	------	------	------	------	-----	-----	----	-----	-------------	-----	------	----

		` ,	
Tdesignh(°C)	-10	Tbiv(°C)	-7
Pdesignh(kW	14.053	TOL(°C)	-10
1)			

# Test result A, B, C, D, E, F conditions:

Condition	Part load	Measured capacity	COP at measured capacity	Cdh	CR	COP at part load
E	14.053	14.005	2.76	0.90	1.00	2.76
F	12.431	12.431	3.34	0.90	1.00	3.34
А	12.431	12.431	3.34	0.90	1.00	3.34
В	7.567	7.574	4.52	0.90	1.00	4.52
С	4.864	8.142	6.38	0.90	0.60	5.98
D	2.162	8.979	8.11	0.90	0.24	6.17
ICB: part load (	divided by can-	acity:				

CR: part load divided by capacity;

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 12 of 32 www.tuvsud.com

TÜV®



Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.039
Standby mode [P <sub>SB</sub> ]	kW	0.013
Crankcase heater [P <sub>CK</sub> ]	kW	0.054
Off mode [P <sub>OFF</sub> ]	kW	0.013

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	4.70
SCOP:	kWh/kWh	4.69
Q <sub>H</sub> :	kWh/year	29033
Q <sub>HE</sub> :	kWh/year	6189
$\eta_{s,h}$	%	184.6
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 2)		A+++

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 13 of 32





Table 4.	Heating mode(Medium temperature application):							P	
Model	SWD WP15 F	WD WP15 R290							
Product	Air to Water	Heating	7	Averag		Warmer		Colder	
type		season		e					
1. Test cond	litions:								
		Part Loa		)		Outdoo	r heat	Indoo	r heat
o		in <sup>c</sup>	%			excha	nger	excha	anger
Condition	Form	nula	Α	W	С	Inlet dry			let water
Š						bul		temperat	ures (°C)
၂						temper °C			
Α	(-7-16)/(Tdesi	anh-16)	88	N/A	N/A	-7(-		a/	52
B	(+2-16)/ (Tdesi		54	N/A	N/A	2(1		a /	
C	(+7-16)/(Tdes		35	N/A	N/A	7(6		a /	
D	(+12-16)/(Tde		15	N/A	N/A	12(1		a /	
Ē		(TOL-16)/ (To				TO			55.3
F		(Tbivalent-16)/(To				Tbi	v	a / 52	
G					N/A	-15 N/A			/A
Remark: a) W 2 at 47/55 con									
2.Tested dat	a/correction	data(Avera	age):						
General test	Unit	A(-7)/W52	A2/	W42	A7/W3	6 A12	/W30	A(-	A(-
conditions/		(88%)	(54	4%)	(35%)	)   (1	5%)	10)/W55.	7)/W52
Part-Load								3	(88%)
								(100%)	
		Α		В	С		D	E	F
Data	hh: min:sec	1:10:00	1:1	0:00	1:10:0	0 1:1	0:00	1:10:00	1:10:00
collection									
period									
The heat		No	١	No ol	No		No.	No	No
pump									
defrosts									
Complete		0		0	0		0	0	0
Cycles									
Barometric	kPa	99.85	99.85 99.8		99.85	99	9.80	99.75	99.85
pressure									
Voltage	V	398.7	39	8.8	398.8	39	8.9	398.6	398.7
Current input	Α	8.20	3.	.88	3.09	2	.68	10.28	8.20
of the unit									
Power input	kW	5.019	2	101	1.635	1	382	6.394	5.019
of the unit									

Project No: 64.181.23.03010.01

Test conditions indoor unit

°C

°C

Rev.: 00 Date: 2023-08-09 Page: 14 of 32

Inlet Water

DB

DB

temperature,

Outlet Water

temperature,

www.tuvsud.com

37.11

41.98

33.03

38.15



44.11

52.06

46.15

55.02

44.11

52.06

Tel: +86 20 38320668

28.65

34.59



Appendix I	est results						
Test condition	s <b>outdoor</b> unit						
Air <b>inlet</b> temperature, DB	°C	-7.00	2.01	7.01	12.02	-10.00	-7.00
Air <b>inlet</b> temperature, WB	°C	-7.95	1.00	6.00	11.03	-10.96	-7.95
Summary of th	ne results						
Total heating capacity	kW	11.913	7.285	7.662	8.886	13.288	11.913
Effective power input	kW	5.004	2.087	1.621	1.368	6.380	5.004
Coefficient of performance (COP)		2.38	3.49	4.73	6.50	2.08	2.38
Compressor frequency	Hz	71	35	30	30	90	71
Water flow	m³/h	1.29	1.29	1.29	1.29	1.29	1.29

Remark: \* In part condition, outlet temperature data is recorded by a full average complete cycle's data. \*\*The inlet and outlet temperatures are been determined according to CI.11.5.1 of EN 14825:2022.

#### 3.Calculation/conclusion for SCOP(Average):

	<b>3</b> -y-							
Tdesignh(°C)	-10	Tbiv(°C)	-7					
Pdesignh(kW	13.467	TOL(°C)	-10					
)								

# Test result A, B, C, D, E, F conditions:

1.000.000.00	, _, _, _, _,					
Condition	Part load	Measured capacity	COP at measured capacity	Cdh	CR	COP at part load
E	13.467	13.288	2.08	0.90	1.00	2.08
F	11.913	11.913	2.38	0.90	1.00	2.38
А	11.913	11.913	2.38	0.90	1.00	2.38
В	7.251	7.285	3.49	0.90	1.00	3.49
С	4.662	7.662	4.73	0.90	0.61	4.44
D	2.072	8.886	6.50	0.90	0.23	4.89
CR: part load	divided by cap	acity;				•

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 15 of 32 www.tuvsud.com

TÜV®



Electric power consumptions	Unit	Value
Thermostat-off mode [P <sub>TO</sub> ]	kW	0.039
Standby mode [P <sub>SB</sub> ]	kW	0.013
Crankcase heater [P <sub>CK</sub> ]	kW	0.054
Off mode [P <sub>OFF</sub> ]	kW	0.013

Conclusions:	Unit	Value
SCOPon:	kWh/kWh	3.55
SCOP:	kWh/kWh	3.55
Q <sub>H</sub> :	kWh/year	27823
Q <sub>HE</sub> :	kWh/year	7844
$\eta_{s,h}$	%	138.9
Seasonal space heating energy efficiency classes: (According (EU) No 811/2013 Table 1)		A++

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 16 of 32





Table 5a.	Sound power leve application)	emperature	P					
Model	SWD WP10 R290							
	Product type :		Air to Water					
	Outdoor heat excha	anger, Air temperature [	DB/WB (°C):	7.0 / 6.0				
	Indoor heat exchan	30.0 / 35.0						
	Voltage (V):	400						
	Frequency (Hz):	50						
	Working condition of	Class A						
	Acoustical environn	Hemi-anechoic room Sponge						
	Windshield type :							
	Measured position							
	Water flow (m³/h):	1.55						
Meas	ured quantity	L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark				
Sound pressure level $\overline{L}_{p(ST)}^{****}$			44	-				
Measuremen	t distance d *		1.0m					
Sound power	level L <sub>wA</sub> ****		59					

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer Fan speed: 400 r/min, compressor speed: 50Hz.

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 17 of 32



Table 5b.	Sound power level application)	Sound power level measurement(Medium temperature application)								
Model	SWD WP10 R290	SWD WP10 R290								
	Product type :	Product type :								
	Outdoor heat excha	nger, Air temperature	DB/WB (°C):	7.0 / 6.0						
	Indoor heat exchang	Indoor heat exchanger, Water inlet/outlet temperature (°C):								
	Voltage (V):	400								
	Frequency (Hz):	50								
	Working condition c	Class A								
	Acoustical environm	Hemi-anechoic room								
	Windshield type :	Sponge								
	Measured position a	14								
	Water flow (m³/h):			0.98						
Meas	sured quantity	L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark						
Sound pressure level $\bar{L}_{p(ST)}^{****}$			45							
Measurement distance d *			1.0m							
Sound powe	r level L <sub>wA</sub> ****		59							
Setting of co	ntrols: according to us	ı er manual		L						

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer Fan speed: 400 r/min, compressor speed: 56Hz.

Doc No.: ITC-TTW0902.02E - Rev.12



Annendix | Test results

Table 6a.	Sound power leve application)	emperature	Р						
Model	SWD WP15 R290	SWD WP15 R290							
	Product type :	Air to Water							
	Outdoor heat excha	anger, Air temperature I	DB/WB (°C):	7.0 / 6.0					
	Indoor heat exchan	ger, Water inlet/outlet t	emperature (°C):	30.0 / 35.0					
	Voltage (V):			400					
	Frequency (Hz):	50							
	Working condition of	Class A							
	Acoustical environn	Hemi-anechoic room							
	Windshield type :	Sponge							
	Measured position	14							
	Water flow (m³/h):		2.24						
Measured quantity		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark					
Sound pressure level $\overline{L}_{p(ST)}^{****}$			45						
Measuremei	nt distance d *		1.0m						
Sound power	r level L <sub>wA</sub> ****		60						
Sotting of on	introls: according to us	ar manual	Brown.						

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer

Fan speed: 400 r/min, compressor speed: 48Hz.





Table 6b.	Sound power leve application)	ım temperature	Р						
Model	SWD WP15 R290	SWD WP15 R290							
	Product type :	Air to Water							
	Outdoor heat exch	Outdoor heat exchanger, Air temperature DB/WB (°C):							
	Indoor heat exchar	47.0 / 55.0							
	Voltage (V):	400							
	Frequency (Hz):	50							
	Working condition	Class A							
	Acoustical environ	Hemi-anechoic room							
	Windshield type :	Sponge							
	Measured position	14							
	Water flow (m³/h):			1.29					
Measured quantity		L <sub>WA,indoors</sub> (dB(A))	L <sub>WA,outdoors</sub> (dB(A))	Remark					
Sound pressure level $\bar{L}_{p(ST)}^{****}$			46	-					
Measuremer	-								
Sound power level L <sub>wA</sub> **** 62									
Sotting of co	entrole: according to u	cor manual							

Setting of controls: according to user manual.

Duct connection:--

Rounding to: \*) 1 decimal places; \*\*) 2 decimal places; \*\*\*) 3 decimal places; \*\*\*\*) nearest integer Fan speed: 400 r/min, compressor speed: 54Hz.

Doc No.: ITC-TTW0902.02E - Rev.12

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 20 of 32

www.tuvsud.com



5F&8F East, Communication Building, No.163 Pingyun Road, Huangpu Ave. West, Guangzhou 510656, China



Table 7.	Clause 4 of	EN 14511-4:	2022		Р
Model	SWD WP10		2022		Г
			Standard	Comment	Test
Customer Code	Execution Date [dd- mm-yyyy]	Testing item	Referenc e	Comment	Test Response
TEST 1	08-06-2023	STARTING TEST	EN14511- 4:2022, § 4.2.1.2 Table 3	The "lower" starting operating conditions declared by the manufacturer for the heating mode- i.e. Tair=-25.12°C, T out water 9.02°C, Flow rate 0.96m³/h have been set and obtained. At those conditions, the machine was switched on. It started without any problem and worked for 30 minutes without showing any warning or allarm. During the test the machine operated in automode. No damage was recorded on the machine during and after the test.	Passed
TEST 2	08-06-2023	OPERATIN G TEST		From the machine "lower" starting conditions - i.e the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair=-25.33°C, T out water 60.09°C, Flow rate 0.96m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in automode. During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.	Passed
TEST 3	08-06-2023	SHUTTING OFF WATER FLOW	EN14511- 4:2022, § 4.5	The water flow rate was shutted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit. Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.	Passed
TEST 4	08-06-2023	SHUTTING OFF AIR FLOW	EN14511- 4:2022, § 4.5	The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally. During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.	Passed
TEST 5	08-06-2023	COMPLET E POWER SUPPLY FAILURE	EN14511- 4:2022, § 4.6	The power supply was cut off for about 10 seconds. The unit restarted automatically within about 3 minutes after the power supply was reactivated.	Passed

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 21 of 32 www.tuvsud.com

T]"N/®



	( I Test resu				
Table 8.		EN 14511-4:	2022		Р
Model	SWD WP15	R290			
Customer Code	Execution Date [dd- mm-yyyy]	Testing item	Standard Referenc e	Comment	Test Response
TEST 1	09-06-2023	STARTING TEST	EN14511- 4:2022, § 4.2.1.2 Table 3	The "lower" starting operating conditions declared by the manufacturer for the heating mode- i.e. Tair=-25.17°C, T out water 9.11°C, Flow rate 1.28m³/h have been set and obtained. At those conditions, the machine was switched on. It started without any problem and worked for 30 minutes without showing any warning or allarm. During the test the machine operated in automode. No damage was recorded on the machine during and after the test.	Passed
TEST 2	09-06-2023	OPERATIN G TEST	EN14511- 4:2022, § 4.2.1.2 Table 3	From the machine "lower" starting conditions - i.e the machine was brought to the lower operating conditions declared by the manufacturer for the heating mode- i.e. Tair=-25.21°C, T out water 60.03°C, Flow rate 1.28m³/h. Once these conditions were obtained, the machine was let operate for over 1 hour in automode. During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.	Passed
TEST 3	09-06-2023	SHUTTING OFF WATER FLOW	EN14511- 4:2022, § 4.5	The water flow rate was shutted off through manual and automatic valves of the test rig. The machine switched off and only the flow switch Protection appeared on the user interface of indoor unit. Perform error reset operation, once the water flow rate was restored, the machine restarted automatically and worked for 30 minutes normally. No damage was recorded on the machine during and after the test.	Passed
TEST 4	09-06-2023	SHUTTING OFF AIR FLOW	EN14511- 4:2022, § 4.5	The air flow rate was shutted off through a plastic sheet and a panel. The machine never turned off. It continued to operate with continuous frosting and defrosting cycles. After more than half an hour, the air flow rate was restored and the machine started to operate normally. During the test, no waring or alarm were showed. No damage was recorded on the machine during and after the test.	Passed
TEST 5	09-06-2023	COMPLET E POWER SUPPLY FAILURE	EN14511- 4:2022, § 4.6	The power supply was cut off for about 10 seconds. The unit restarted automatically within about 3 minutes after the power supply was reactivated.	Passed

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 22 of 32



# Appendix II Marking plate

### Nameplate

# Model: SWD WP10 R290

DC Inverte	r Heat Pump
Model	SWD WP10 R290
Power supply	380-415V/3N~/50 Hz
*Heating Capacity Range	5.9∼14.8 k₩
*Heating input Range	1.13~3.83 kW
**Cooling capacity Range	4. 3~10. 8 kW
**Cooling input power	1. 39~3. 99 kW
***Heating capacity Range(DWH)	6. 6∼13. 2 k₩
***Heating input Range(DWH)	1.41~3.73 kW
Rated Current	3. 72 A
Rated Power Input	2.08 kW
Refrigerant	R290/1150 g
Max operating pressure (High side)	3.2 MPa
Max operating pressure (Low side)	0.8 MPa
Maximum allowable pressure	3. 2 MPa
Climate type	Low Temperature
Operating range	− 25~43°C
Water Flow	2,55m <sup>3</sup> /h
Diameter of pipe	DN25
IP Grade	IPX4
Electric shock rating	
Body size(W×D×H)	1080×480×1060 mm
Net weight/Gross weight	138/150 kg
Production date and code	See unit barcode

Sonnenwärme Direkt GmbH

Dammholmer Str. 3, 24873 Havetoft, Germany

#### Remark:

\*Heating working condition: Inlet water temperature 30°C, Outlet water temperature 35°C Dry bulb temperature 7°C, Wet bulb temperature 6°C.

\*\*Cooling working condition: Inlet water temperature 12°C, Outlet water temperature 7°C Dry bulb temperature 35°C, Wet bulb temperature 24°C.

\*\*\*DHW working condition: Inlet water temperature 15°C, Outlet water temperature 55°C Dry bulb temperature 7°C, Wet bulb temperature 6°C.





Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 23 of 32





Appendix II Marking plate

### Nameplate

# Model: SWD WP15 R290

DC Inverte	r Heat Pump
Model	SWD WP15 R290
Power supply	380-415V/3N~/50 Hz
*Heating Capacity Range	8.8~22.0 kW
*Heating input Range	1. 68∼5. 77 k₩
**Cooling capacity Range	6. 2~15. 3 kW
**Cooling input power	1.99~5.60 kW
***Heating capacity Range(DWH)	7.8~17.6 kW
***Heating input Range(DWH)	1. 67~5. 01 kW
Rated Current	5. 01 A
Rated Power Input	2. 80 kW
Refrigerant	R290/1400 g
Max operating pressure (High side)	3. 2 MPa
Max operating pressure (Low side)	0.8 MPa
Maximum allowable pressure	3. 2 MPa
Climate type	Low Temperature
Operating range	− 25~43°C
Water Flow	3. 78m³/h
Diameter of pipe	DN25
IP Grade	IPX4
Electric shock rating	
Body size( $W \times D \times H$ )	1080×480×1372 mm
Net weight/Gross weight	170/185 kg
Production date and code	See unit barcode

Dammholmer Str. 3, 24873 Havetoft, Germany

\*Heating working condition: Inlet water temperature 30°C, Outlet water temperature 35°C Dry bulb temperature 7°C, Wet bulb temperature 6°C.

\*\*Cooling working condition: Inlet water temperature 12°C, Outlet water temperature 7°C Dry bulb temperature 35°C, Wet bulb temperature 24°C.

\*\*\*DHW working condition: Inlet water temperature 15°C, Outlet water temperature 55°C Dry bulb temperature 7°C, Wet bulb temperature 6°C.





Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 24 of 32



Appendix III photo documentaiton

Details of:	Overall view for SWD WP10 R290	
View:		
☐ General		
☐ Front		
☐ Rear		
□ Right		
□ Left		
□ Тор		
□ Bottom		



Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 25 of 32





Appendix III photo documentaiton



View:  General Front Rear Right Left Do Top Bottom	

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 26 of 32





Details of:	Water Pump for SWD WP10 R290				
View:	High Efficiency Circulation Pump				
☐ General ☐ Front	Model:APM25-9-130 PWM1 Serial No. EEIs0.21-Part3				
□ Rear	TF110 IP44 Class F 230V 50/60Hz				
□ Right	I(A) P (W) Mpa H(m)				
	Min. 0.04 4 - 1				
□ Left	Max. 0.75 95 1.0 9				
□ Тор	CEX				
□ Bottom	MADE IN CHINA				
	Add. Ruisheng Road 1#, Economical development Zone, Shuyang City.				

Details of:	Overall view for SWD WP15 R290		
View:			
☐ General			
☐ Front			
□ Rear			
☐ Right			
□ Left			
□ Тор			
□ Bottom			

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 27 of 32





Appendix III photo documentaiton

Details of:	Compressor for SWD WP15 R290
View:  General  Front  Rear  Right  Left  Top  Bottom	HIGHLY WHP32900VSKTQ9JK 2012 RoHS 900-6800r/min(at 3800 r/min) 2022,11.15a R290/R454B/R454C/R134a  W82N1E02QNL8  上海和文化度有限公司、SFMMBMI, NÍGALY, ELECTRICAL APPLIANCES 02. LTD.

Details of:	Fan Motor for SWD WP15 R290
View:	
☐ General	DD 150日A 空气调节器用型封无刷直流电动机
☐ Front	JOSIOV 150W (FAN MOTOR FOR AIR CONDITIONER)
□ Rear	0,60A E级(CL) 红 RD Vm· (T)
☐ Right	88k(P) 850r/min 黄 YE Vsp
□ Left	(Mangmen LT Molor Co., Lld)
□ Тор	Q.O.Pass
□ Bottom	RoHS 000332 20220808

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 28 of 32





Appendix III photo Details of:	Main Control Board for SWD WP15 R290
View:  General Front Rear Right Left	
□ Top □ Bottom	



Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 29 of 32





# Appendix IV Construction data form

Model: SWD WP10 R290			
Part		Technical data	
1. Compressor			
	Manufacture:	Shanghai Highly Electrical Appliance Co., Ltd.	
	Type:	WHP13300PSDPC8FQ	
	Rated capacity:	2860W	
	Serial-number:	W6PN5H06JKMJ	
	Specification:	DC143.5V; 900-6600r/min; R290	
2. Condenser			
	Manufacture:	Ningbo Hrale Plate Heat Exchanger Co., Ltd.	
	Type:	B3-68-34-4.5	
	Heat exchanger:	Plate heat exchanger	
	Dimension(mm):	119(L)mmX526(H)mmX89.5(D)mm	
3. Evaporator			
	Manufacture:	Guangzhou AOTAI Refrigeration Equipment Co.,LTD	
	Туре:	801002-1154	
	Heat exchanger:	Finned heat exchanger	
	Dimension(mm):	764*345*990*Φ7.94*3	
4. Fan motor			
	Manufacture:	Jiangmen LT Motor Co., Ltd	
	Туре:	RD200HC	
	Fan type:	3 blade	
	Specification:	DC310V; 200W	
5. Main control board			
	Manufacture:	Guangdong Chico Electronic Inc.	
	Туре:	PW58341	
	Specification:	380V; 50Hz	
6. Water pump			
	Manufacture:	SHIMGE PUMP INDUSTRY(JIANGSU)CO.,LTD.	
	Type:	APM25-9-130 PWM1	
	Specification:	230V; 50/60Hz; 4-95W	

Project No: 64.181.23.03010.01

Rev.: 00 Date: 2023-08-09 Page: 30 of 32





# Appendix IV Construction data form

Model: SWD WP15	R290	
Part		Technical data
1. Compressor		
	Manufacture:	Shanghai Highly Electrical Appliance Co., Ltd.
	Type:	WHP32900VSKTQ9JK
	Rated capacity:	4330W
	Serial-number:	W82N1E02QNL8
	Specification:	DC221V; 900-6600r/min; R290
2. Condenser		
	Manufacture:	Danfoss (Jiaxing) Plate Heat Exchanger Co., LTD
	Type:	C39L-EZ-54
	Heat exchanger:	Plate heat exchanger
	Dimension(mm):	118(L)mmX332(H)mmX74(D)mm
3. Evaporator		
	Manufacture:	Guangzhou AOTAI Refrigeration Equipment Co.,LTD
	Type:	801002-1439
	Heat exchanger:	Finned heat exchanger
	Dimension(mm):	760*265*1300*Ф7.94*2
4. Fan motor		
	Manufacture:	Jiangmen LT Motor Co., Ltd
	Type:	RD150HA
	Fan type:	3 blade
	Specification:	DC310V; 150W
5. Main control board		
	Manufacture:	Guangdong Chico Electronic Inc.
	Type:	PW58339
	Specification:	380V; 50Hz
6. Water pump		
	Manufacture:	SHIMGE PUMP INDUSTRY(JIANGSU)CO.,LTD.
	Type:	APF25-12-130E FPWM1
	Specification:	230V; 50/60Hz; 10-180W

Rev.: 00 Date: 2023-08-09 Page: 31 of 32

www.tuvsud.com





**Appendix V Equipment List** 

No.	Туре	Manufacture	Model	Equipment ID	Calibration Due Date
1	Heat pump energy efficiency testing system	PINXIN	10HP	2017J00001	2023-11-24
2	Electromagnetic flowmeter	KROHNE	OPTIFLUX4100 C	H17221264	2023-12-21
3	Anechoic rooms (hemi-anechoic rooms)	Guangzhou Kinte	-	NC-036-2	2023-10-07
4	AC source Supply	YANGHONG	YF-3600	VGDS-0637	2023-11-07
5	6 channel data logger	_	PXI-1033	VGDY-0257	2024-05-20
6	PULSE system	B & K	3660C	VGDY-0184	2024-04-12
7	Calibrator	B & K	4231	HJ-000095	2023-06-30
8	Long steel tape	<del>-</del>	5m	HJ-000150	2024-01-01
9	Temperature measurement system	_	_	NC-036-1	2024-06-07
10	Atmospheric pressure meter	_	_	HJ-000165	2023-11-22
11	Constant temperature water system	B & K	_	VGDS-0448	2024-04-18
12	Windscreen	B & K	WS002-5	_	_

-- End of Report --



Rev.: 00 Date: 2023-08-09 Page: 32 of 32

